

CR LAURENCE CO., INC. TEST REPORT

SCOPE OF WORK

AIR / WATER / STRUCTURAL TESTING ON BT525 WINDOW WALL SYSTEM

REPORT NUMBER

I1399.01-303-47 R1

TEST DATE

02/23/18

ISSUE DATE

03/02/18

REVISION DATE

03/07/18

RECORD RETENTION END DATE

02/23/22

PAGES


14

DOCUMENT CONTROL NUMBER

ATI 00479 (07/24/17)

RT-R-AMER-Test-2805

© 2017 INTERTEK



TEST REPORT FOR CR LAURENCE CO., INC.

Report No.: I1399.01-303-47 R1

Date: 03/02/18

REPORT ISSUED TO

CR LAURENCE CO., INC.

2503 E. Vernon Avenue
Los Angeles, California 90058

SECTION 1

SCOPE

Intertek Building & Construction (B&C) was contracted by CR Laurence Co., Inc., 2503 E. Vernon Avenue to perform testing in accordance with AAMA 501, *Methods of Test for Exterior Walls*, on their BT525, Window Wall System. Results obtained are tested values and were secured by using the designated test method(s). Testing was conducted at CR Laurence Co., Inc. test facility in Los Angeles, California.

This report does not constitute certification of this product nor an opinion or endorsement by this laboratory.

SECTION 2

SUMMARY OF TEST RESULTS

TITLE	RESULTS
Design Pressure	±1200 Pa (±25.0 psf)
Air Infiltration @ 1.57 psf	0.1 L/s/m ² (0.01 cfm/ft ²)
Air Infiltration @ 6.27 psf	0.1 L/s/m ² (0.02 cfm/ft ²)
Water Penetration Resistance Test Pressure	580 Pa (12.11 psf)
Uniform Load Structural Test Pressure	±1800 Pa (±37.59 psf)

For INTERTEK B&C:

COMPLETED BY:	Jarod S. Hardman
TITLE:	Laboratory Manager
SIGNATURE:	
DATE:	03/07/18

jsh:ss/ms

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to permit copying or distribution of this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of the tested material, product or service must first be approved in writing by Intertek. The observations and test results in this report are relevant only to the sample(s) tested. This report by itself does not imply that the material, product, or service is or has ever been under an Intertek certification program.

TEST REPORT FOR CR LAURENCE CO., INC.

Report No.: I1399.01-303-47 R1

Date: 03/02/18

SECTION 3

TEST METHOD(S)

The specimens were evaluated in accordance with the following:

AAMA 205-15, *In-Plant Testing Guidelines for Manufacturers and Independent Laboratories*

AAMA 501.1-17, *Standard Test Method for Water Penetration of Windows, Curtain Walls and Doors using Dynamic Pressure*

ASTM E283-04(2012), *Standard Test Method for Determining Rate of Air Leakage Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen*

ASTM E330/E330M-14, *Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference*

ASTM E331-00(2016), *Standard Test Method for Water Penetration of Exterior Windows, Skylights, Doors, and Curtain Walls by Uniform Static Air Pressure Difference*

SECTION 4

MATERIAL SOURCE/INSTALLATION

Test specimen was provided by the client.

The specimen was installed into a Spruce-Pine-Fir wood buck. The rough opening allowed for a 3/8" shim space. The interior and exterior perimeter of the window were sealed with structural silicone sealant. Installation of the tested product was performed by the client.

LOCATION	ANCHOR DESCRIPTION	ANCHOR LOCATION
Through Frame	#10 x 2-1/2" PH SMS	6" from each corner and 17-3/4" on center spacing at head and sill, 6" from each corner and 17-3/4" on center spacing at jambs, see attached drawings.

SECTION 5

EQUIPMENT

Calibration of test equipment was performed by Intertek B&C in accordance with AAMA 205-15 "In-Plant Testing Guidelines for Manufacturers and Independent Laboratories"

TEST REPORT FOR CR LAURENCE CO., INC.

Report No.: I1399.01-303-47 R1

Date: 03/02/18

SECTION 6

LIST OF OFFICIAL OBSERVERS

NAME	COMPANY
Garrett Osterode	CR Laurence Co., Inc.
Charles Presley	Intertek B&C
Jarod Hardman	Intertek B&C

SECTION 7

TEST SPECIMEN DESCRIPTION

Product Type: Window Wall System

Series/Model: BT525

Product Size:

OVERALL AREA:	WIDTH		HEIGHT	
	Millimeters	Inches	Millimeters	Inches
10.7 m ² (114.7 ft ²)				
Overall Size	3886	153	2743	108

Frame Construction:

FRAME MEMBER	MATERIAL	DESCRIPTION
Head and Sill	Aluminum	Part No. BT56811 (<i>See attached drawings</i>)
Head and Sill	Aluminum	Part No. BG56611, Head/Sill Insert, snap fit into frame extrusion on interior side of glazing (<i>See attached drawings</i>)
Horizontal Mullion	Aluminum	Part No. BT56311 (<i>See attached drawings</i>)
Horizontal Mullion	Aluminum	Part No. BG30611, Insert Flat, snap fit into horizontal mullion extrusion on interior side of glazing (<i>See attached drawings</i>)
Horizontal Mullion	Aluminum	Part No. AP555, Shear Block, secured at ends of horizontal mullions with two screws (<i>See attached drawings</i>)
Horizontal Mullion	Aluminum	Part No. BG35511, F-Cap, snap fit onto horizontal mullion extrusion on exterior side of glazing (<i>See attached drawings</i>)

TEST REPORT FOR CR LAURENCE CO., INC.

Report No.: I1399.01-303-47 R1

Date: 03/02/18

Frame Construction (Continued):

FRAME MEMBER	MATERIAL	DESCRIPTION
Jambs	Aluminum	Part No. BT56911 (See attached drawings)
Jambs	Aluminum	Part No. BG56011, snap fit into jamb extrusion at interior side of glazing (See attached drawings)
Vertical Mullion	Aluminum	Part No. BG55011 (See attached drawings)
Vertical Mullion	Aluminum	Part No. RG638, Thermal Clip, press fit into vertical mullion at exterior face of left vertical mullion (See attached drawings)
Vertical Mullion	Aluminum	Part No. BG35411, F-Cap, press fit onto Thermal Clip at exterior side of glazing at left vertical mullion (See attached drawings)
	JOINERY TYPE	DETAIL
All Corners	Flush	Secured through jambs with #12 x 1-3/4" PH SMS

Reinforcement:

PART NUMBER	LOCATION	MATERIALS
SS550	Inserted into vertical mullions	Steel

Weatherstripping: No weatherstripping was utilized.

Glazing: No conclusions of any kind regarding the adequacy or inadequacy of the glass in any glazed test specimen(s) can be made.

GLASS TYPE	SPACER TYPE	INTERIOR LITE	EXTERIOR LITE	GLAZING METHOD
1" IG	Aluminum Spacer – Dual Seal (A1-D)	1/4" clear tempered	1/4" clear tempered	Exterior glazed with spacer Part No. SP455 and 95C silicone sealant at interior; exterior glazing was either dry glazed with gasket Part No. NP255 or wet glazed with 95C silicone sealant (See attached drawings)

TEST REPORT FOR CR LAURENCE CO., INC.

Report No.: I1399.01-303-47 R1

Date: 03/02/18

LOCATION	QUANTITY	DAYLIGHT OPENING		GLASS BITE
		Millimeters	Inches	
Upper Fixed Lite (Center and Right)	2	1219 x 1683	48 x 66-1/4	7/16" - 27/32"
Upper Fixed Lite (Left)	1	1219 x 1683	48 x 66-1/4	7/16" - 3/4"
Lower Fixed Lite (Center and Right)	2	1219 x 889	48 x 35	7/16" - 27/32"
Lower Fixed Lite (Left)	1	1219 x 889	48 x 35	7/16" - 3/4"

Drainage: *No drainage was utilized.*

Hardware: *No hardware was utilized.*

Screen Construction: *No screen was utilized.*

TEST REPORT FOR CR LAURENCE CO., INC.

Report No.: I1399.01-303-47 R1

Date: 03/02/18

SECTION 8
TEST RESULTS

The temperature during testing was 13°C (56°F). The results are tabulated as follows:

TITLE OF TEST	RESULTS	ALLOWED	NOTE
Uniform Load Preload, per ASTM E330 +600 Pa (+12.53 psf)	N/A	N/A	
Air Leakage, Infiltration per ASTM E283 at 75 Pa (1.57 psf)	0.1 L/s/m ² (0.01 cfm/ft ²)	0.3 L/s/m ² (0.06 cfm/ft ²) max.	1
Air Leakage, Infiltration per ASTM E283 at 300 Pa (6.27 psf)	0.1 L/s/m ² (0.02 cfm/ft ²)	0.3 L/s/m ² (0.06 cfm/ft ²) max.	1
Water Penetration, per ASTM E331 at 580 Pa (12.11 psf)	Pass	No leakage	
Uniform Load Deflection, per ASTM E330 Deflections taken at vertical mullion +1200 Pa (+25.09 psf) -1200 Pa (-25.09 psf)	12.4 mm (0.49") 15.7 mm (0.62")	15.7 mm (0.62") max. 15.7 mm (0.62") max.	2
Air Leakage, Infiltration per ASTM E283 at 75 Pa (1.57 psf)	0.1 L/s/m ² (0.01 cfm/ft ²)	0.3 L/s/m ² (0.06 cfm/ft ²) max.	1
Air Leakage, Infiltration per ASTM E283 at 300 Pa (6.27 psf)	0.1 L/s/m ² (0.02 cfm/ft ²)	0.3 L/s/m ² (0.06 cfm/ft ²) max.	1
Water Penetration, per ASTM E331 at 580 Pa (12.11 psf)	Pass	No leakage	
Water Penetration, per AAMA 501.1 at 580 Pa (12.11 psf)	Pass	No leakage	

TEST REPORT FOR CR LAURENCE CO., INC.

Report No.: I1399.01-303-47 R1

Date: 03/02/18

TITLE OF TEST	RESULTS	ALLOWED	NOTE
Uniform Load Structural, per ASTM E330 Permanent set taken at vertical mullion +1800 Pa (+37.59 psf) -1800 Pa (-37.59 psf)	 0.5 mm (0.02") 0.3 mm (0.01")	 5.6 mm (0.22") max. 5.6 mm (0.22") max.	 2

General Note: All testing was performed in accordance with the referenced standard(s).

Note 1: Test Date 02/23/18 / Time: 6:30 AM

Note 2: Loads were held for 10 seconds.

TEST REPORT FOR CR LAURENCE CO., INC.


Report No.: I1399.01-303-47 R1

Date: 03/02/18

SECTION 9

LOCATION OF AIR SEAL

The air seal between the test specimen and the test wall is detailed below. The seal is made of foam weatherstripping and is attached to the edge of the test specimen buck. The test specimen buck is placed against the test wall and clamped in place, compressing the weatherstripping and creating a seal.





Total Quality. Assured.

25800 Commercentre Drive
Lake Forest, California 92630

Telephone: 949-460-9600
Facsimile: 717-764-4129
www.intertek.com/building


TEST REPORT FOR CR LAURENCE CO., INC.

Report No.: I1399.01-303-47 R1

Date: 03/02/18

SECTION 10
DRAWINGS

The test specimen drawings have been reviewed by Intertek B&C and are representative of the test specimen(s) reported herein. Any deviations are documented herein or on the drawings.



ITEM	PT. NO.	PART DESCRIPTION
C1	BT56811	CRL U.S. ALUMINUM HEAD/SILL
C2	BT56311	CRL U.S. ALUMINUM HORIZONTAL MULLION
C3	BG55011	CRL U.S. ALUMINUM VERTICAL MULLION
C4	BG35411	CRL U.S. ALUMINUM F-CAP/CAPTURE
C5	BG56611	CRL U.S. ALUMINUM HEAD/SILL INSERT
C6	BT56911	CRL U.S. ALUMINUM JAMB-BASE EXTRUSION
C7	BG56011	CRL U.S. ALUMINUM JAMB-MULLION EXTRUSION
C8	RG638	CRL U.S. ALUMINUM THERMAL CLIP
C9	AP555	CRL U.S. ALUMINUM SHEAR BLOCK W/SCREWS
C10	BG30611	CRL U.S. ALUMINUM INSERT. FLT. SNAP-IN
C11	SS550	CRL U.S. ALUMINUM STEEL STIFFENER
C12	BG35511	CRL U.S. ALUMINUM F-CAP, EXT/INT
W1	SP455	EDPM SPACER
W2	NP225	CRL STOREFRONT GASKET
G1		.025 X .050 X .025 INSULATED GLASS (TEMPERED) ALUMINUM SPACER-DUAL GLAZED
G2	SB110	NEOPRENE SETTING BLOCK
G3	SB334	NEOPRENE SETTING BLOCK
G4	BG338	CHAIR, SETTING BLOCK
G5	UB625	BAFFLE, URETHANE
H2	EF12	CRL CLOSED CELL 1/2" DIA. BACKER ROD
H3	DC795	DOW CORNING 795 BUILDING SEALANT
H4	RTV408C	CRL CLEAR RTV408 NEUTRAL CURE SILICONE
H5	---	#10 X 2 1/2" PH SMS
H6	ST-267	#12 X 1-3/4" PH SMS
H7	SD525	END DAM-HEAD & SILL
H8	95C	SILICONE BUILDING SEALANT
WD1	WD524	WATER DEFLECTOR @ CORNER
WD2	WD525	WATER DEFLECTOR @ HORIZONTAL MULLION
WD3	WD526	WATER DEFLECTOR @ JAMB

TEST REQUIREMENTS

AIR INFILTRATION:
 <.06 CFM/SQ.FT. @ 1.57 PSF
 <.06 CFM/SQ.FT. @ 6.24 PSF

STATIC WATER:
 12 PSF

DESIGN PRESSURE:
 25 PSF

STRUCTURAL OVERLOAD:
 37.5 PSF

TESTING SEQUENCE:
 Pre Load
 Air
 Water
 Dynamic
 Design Pressure
 Air
 Water
 Structural Overload

intertek Total Quality. Assured.

Report #: 11399-303-47
 Date: 03/01/18
 Verified by: [Signature]

REVISIONS

CRL C.R. LAURENCE CO. ARCHITECTURAL PRODUCTS
 2100 E. 38TH Street, Los Angeles, CA 90058
 www.crlaurence.com

BT525 WINDOW WALL SYSTEM

Job Name: _____
 Glazing Contractor: _____

DATE: 8.31.2017
 DRAWN BY: GDO
 CHECKED BY: XX
 SCALE: AS SHOWN
 JOB #: PTC694433

SHT 1 OF 3

REVISIONS




C.R. LAURENCE CO.
ARCHITECTURAL PRODUCTS
2100 E. 38TH Street, Los Angeles, CA 90058
www.crlaurence.com

BT525 WINDOW WALL SYSTEM


Job Name:

Glazing Contractor:


DATE: 8.31.2017
DRAWN BY: GDO
CHECKED BY: XX
SCALE: AS SHOWN
JOB #: PTC694433




① SECTION DETAIL AT JAMB
ARCH REF: N/A 1'-0"=1'-0"



② SECTION DETAIL AT VERTICAL
ARCH REF: N/A W / FACE CAP 1'-0"=1'-0"




③ SECTION DETAIL AT VERTICAL
ARCH REF: N/A 1'-0"=1'-0"




④ SECTION DETAIL AT JAMB
ARCH REF: N/A 1'-0"=1'-0"


	Report #:	11399-303-47
	Date:	03/01/18
	Verified by:	<i>[Signature]</i>



⑤ SECTION DETAIL AT HEAD
 ARCH REF: N/A 1'-0"=1'-0"



⑥ SECTION DETAIL AT INTERMEDIATE HORIZONTAL
 ARCH REF: N/A 1'-0"=1'-0"



⑦ SECTION DETAIL AT SILL
 ARCH REF: N/A 1'-0"=1'-0"

	Report #:	11399-303-47
	Date:	03/01/18
	Verified by:	<i>[Signature]</i>

REVISIONS

C.R. LAURENCE CO.
 ARCHITECTURAL PRODUCTS
 2100 E. 38TH Street, Los Angeles, CA 90058
 www.crlaurence.com

Job Name: BT525 WINDOW WALL SYSTEM

Glazing Contractor: _____

DATE:	8.31.2017
DRAWN BY:	GDO
CHECKED BY:	XX
SCALE:	AS SHOWN
JOB #:	PTC694433



Total Quality. Assured.

25800 Commercentre Drive
Lake Forest, California 92630

Telephone: 949-460-9600
Facsimile: 717-764-4129
www.intertek.com/building

TEST REPORT FOR CR LAURENCE CO., INC.

Report No.: I1399.01-303-47 R1

Date: 03/02/18

SECTION 11

REVISION LOG

REVISION #	DATE	PAGES	REVISION
0	03/02/18	N/A	Original Report Issue
1	03/07/18	1	Correct testing date to February from March