



TEST REPORT

Report No.: F8220.01-301-47

Rendered to:

CR LAURENCE CO., INC.
Vernon, California

PRODUCT TYPE: Store Front
SERIES/MODEL: TT601-Unit Glazed

Title	Summary of Results
Design Pressure	±1920 Pa (±40.10 psf)
Air Infiltration	0.2 L/s/m ² (0.03 cfm/ft ²)
Water Penetration Resistance Test Pressure	580 Pa (12.11 psf)
Uniform Load Structural Test Pressure	±2880 Pa (±60.15 psf)

Reference must be made to Report No. F8220.01-301-47, dated 05/26/16 for complete test specimen description and detailed test results.

- 1.0 Report Issued To:** CR Laurence Co., Inc.
2100 East 38th St.
Vernon, California 90058
- 2.0 Test Laboratory:** Architectural Testing, Inc., an Intertek company ("Intertek-ATI")
4 Rancho Circle
Lake Forest, California 92630
949-460-9600

3.0 Project Summary:

- 3.1 Product Type:** Store Front
- 3.2 Series/Model:** TT601-Unit Glazed
- 3.3 Compliance Statement:** Results obtained are tested values and were secured by using the designated test methods. Test specimen description and results are reported herein.
- 3.4 Test Dates:** 04/29/16 – 05/04/16
- 3.5 Test Record Retention End Date:** All test records for this report will be retained until May 4, 2020.
- 3.6 Test Location:** CR Laurence Co., Inc. test facility in Vernon, California. Calibration of test equipment was performed by Intertek-ATI in accordance with AAMA 205-01 "In-Plant Testing Guidelines for Manufacturers and Independent Laboratories".
- 3.7 Test Specimen Source:** The test specimen was provided by the client. Representative samples of the test specimen will be retained by Intertek-ATI for a minimum of four years from the test completion date.
- 3.8 Drawing Reference:** The test specimen drawings have been reviewed by Intertek-ATI and are representative of the test specimen(s) reported herein. Test specimen construction was verified by Intertek-ATI per the drawings located in Appendix B. Any deviations are documented herein or on the drawings.

3.9 List of Official Observers:

<u>Name</u>	<u>Company</u>
Garrett Osterode	CR Laurence Co., Inc.
Ron Wooten	CR Laurence Co., Inc.
Jarod Hardman	Intertek-ATI

4.0 Test Methods:

ASTM E283-04 (2012), *Test Method for Determining Rate of Air Leakage Through Exterior Windows, Curtain Walls and Doors Under Specified Pressure Differences Across the Specimen*

ASTM E330/E330M-14, *Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference*

ASTM E331-00 (2009), *Test Method for Water Penetration of Exterior Windows, Skylights, Doors, and Curtain Walls by Uniform Static Air Pressure Difference*

AAMA 501-15, *Methods of Test for Exterior Walls*

AAMA 501.1-05, *Standard Test Method for Water Penetration of Windows, Curtain Walls and Doors using Dynamic Pressure*

5.0 Test Specimen Description:

5.1 Product Sizes:

Overall Area: 10.13 m ² (109.02 ft ²)	Width		Height	
	millimeters	inches	millimeters	inches
Overall size	3310	130-5/16	3060	120-15/32

5.2 Frame Construction:

Frame Member	Material	Description
Head	Aluminum	Head compensation channel, Part No. RT63011, with aluminum glazing bead Part No. RW62211.
Head	Aluminum	Header extrusion, Part No. RT65211, with aluminum glass stop Part No. RW65311.
Horizontal mullion	Aluminum	Horizontal mullion, Part No. RT66311, with aluminum glass stop Part No. RW65311.
Sill	Aluminum	Sub sill extrusion, Part No. FF70011.
Sill	Aluminum	Sill extrusion, Part No. RT66411.

5.0 Test Specimen Description: (Continued)

5.2 Frame Construction: (Continued)

Frame Member	Material	Description
Jamb	Aluminum	Vertical jamb mullion, Part No. RT65511, with aluminum vertical mullion caps.
Vertical mullion	Aluminum	Vertical mullion female, Part No. RT76911.
Vertical mullion	Aluminum	Vertical mullion male, Part No. RT76111.
Sill	Aluminum	End dam, Part No. EC806.

	Joinery Type	Detail
All corners	Flush	Secured through jambs at frame corners with #8 x 5/8" Phillips Tek screws and through vertical mullions with #10 x 1" Phillips washer head sheet metal screws.

5.3 Reinforcement: No reinforcement was utilized.


5.4 Weatherstripping: No weatherstripping was utilized.

5.5 Glazing: *No conclusions of any kind regarding the adequacy or inadequacy of the glass in any glazed test specimen(s) can be made.*

Glass Type	Spacer Type	Interior Lite	Exterior Lite	Glazing Method
1" IG	Aluminum Spacer – Dual Seal (A1-D)	1/4" clear tempered	1/4" clear tempered	Dry glazed system with roll in gasket

5.0 Test Specimen Description: (Continued)

5.5 Glazing: (Continued)



Location	Quantity	Daylight Opening		Glass Bite
		millimeters	inches	
Upper fixed lite (1)	1	1003 x 2032	39-1/2 x 80	1/2"
Upper fixed lite (2)	1	1003 x 2032	39-1/2 x 80	1/2"
Upper fixed lite (3)	1	1003 x 2032	39-1/2 x 80	1/2"
Lower fixed lite (4)	1	1003 x 787	39-1/2 x 31	1/2"
Lower fixed lite (5)	1	1003 x 787	39-1/2 x 31	1/2"
Lower fixed lite (6)	1	1003 x 787	39-1/2 x 31	1/2"

5.6 Drainage:

Method	Size	Quantity	Location
Weep hole	1-1/4" x 1/8"	5	12" from the corner and 24" on center spacing

5.7 Hardware: No hardware was utilized.

5.8 Screen Construction: No screen was utilized.

6.0 Installation:

The specimen was installed into a Pine wood buck. The rough opening allowed for a 1/4" shim space. The interior and exterior perimeter of the window was sealed with silicone sealant.

Location	Anchor Description	Anchor Location
Comp channel	1/4" x 2-1/2" lag bolts	6" from the corners and 18" on center spacing

7.0 Test Results: The temperature during testing was 19°C (66°F). The results are tabulated as follows:

Title of Test	Results	Allowed	Note
Air Leakage, per ASTM E283 at 75 Pa (1.57 psf) at 300 Pa (6.27 psf)	0.2 L/s/m ² (0.03 cfm/ft ²)	0.3 L/s/m ² (0.06 cfm/ft ²) max.	
Water Penetration, per ASTM E331 at 580 Pa (12.11 psf)	Pass	No leakage	
Uniform Load Preload, per ASTM E330 +960 Pa (+20.05 psf)	-	-	1, 2
Air Leakage, per ASTM E283 at 75 Pa (1.57 psf) at 300 Pa (6.27 psf)	0.1 L/s/m ² (0.01 cfm/ft ²)	0.3 L/s/m ² (0.06 cfm/ft ²) max.	3
Water Penetration, per ASTM E331 at 580 Pa (12.11 psf)	Pass	No leakage	3
Water Penetration, per AAMA 501.1 at 580 Pa (12.11 psf)	Pass	No leakage	3
Uniform Load Deflection, per ASTM E330 Deflections taken at vertical mullion +1920 Pa (+40.10 psf) -1920 Pa (-40.10 psf)	8.4 mm (0.33") 9.4 mm (0.37")	17.5 mm (0.69") max. 17.5 mm (0.69") max.	1, 2

7.0 Test Results: (Continued)

Title of Test	Results	Allowed	Note
Air Leakage, per ASTM E283 at 75 Pa (1.57 psf) at 300 Pa (6.27 psf)	$<0.1 \text{ L/s/m}^2$ (<0.01 cfm/ft ²)	0.3 L/s/m^2 (0.06 cfm/ft ²) max.	4
Water Penetration, per ASTM E331 at 580 Pa (12.11 psf)	Pass	No leakage	4
Uniform Load Structural, per ASTM E330 Permanent sets taken at vertical mullion +2880 Pa (+60.15 psf) -2880 Pa (-60.15 psf)	0.5 mm (0.02") 0.5 mm (0.02")	6.1 mm (0.24") max. 6.1 mm (0.24") max.	1, 2

General Note: All testing was performed in accordance with the referenced standard(s).

Note 1: Loads were held for 10 seconds.

Note 2: Tape and film were to seal against air leakage during structural testing. In our opinion, the tape and film did not influence the results of the test.


Note 3: Test performed after the application of uniform load preload.

Note 4: Test performed after the application of uniform load deflection load.

Intertek-ATI will service this report for the entire test record retention period. Test records such as detailed drawings, datasheets, representative samples of test specimens, or other pertinent project documentation, will be retained by Intertek-ATI for the entire test record retention period.

This report does not constitute certification of this product nor an opinion or endorsement by this laboratory. It is the exclusive property of the client so named herein and relates only to the specimen(s) tested. This report may not be reproduced, except in full, without the written approval of Intertek-ATI.

For ARCHITECTURAL TESTING, INC.:



Digitally Signed by: Jarod Hardman

Jarod S. Hardman
Laboratory Manager

JSH:ss

Attachments (pages): This report is complete only when all attachments listed are included.

Appendix A: Location of air seal (1)


Appendix B: Drawings (14)

Revision Log

Rev. #	Date	Page(s)	Revision(s)
0	05/17/16	N/A	Original report issue.
1	05/24/16	Cover, 1	Updated series/model information
1	05/24/16	3	Update part number and description of vertical male and female mullions.
1	05/24/16	6	Add reference to Note 4 of testing results into result tables.
1	05/24/16	Appendix B	Revised drawing included to show internal sealant joints of vertical mullion assembly drawing.
2	05/26/16	Appendix B	Added drawings.

Appendix A


Location of Air Seal: The air seal between the test specimen and the test wall is detailed below. The seal is made of foam weatherstripping and is attached to the edge of the test specimen buck. The test specimen buck is placed against the test wall and clamped in place, compressing the weatherstripping and creating a seal.



Appendix B

Drawings

REVISIONS	



2100 E. 38TH Street, Los Angeles, CA 90058
www.crlaurence.com

TT601 UNIT GLAZE
VERTICAL MULLION

Job Name:


Glazing Contractor:

DATE:	4-1-2015
DRAWN BY:	GDO
CHECKED BY:	XX
SCALE:	AS SHOWN
JOB #:	PTC467035

SHT 1 OF 4

ITEM	PT. NO.	PART DESCRIPTION
C1	RT66411	CRL U.S. ALUMINUM SILL EXTRUSION
C2	RT66211	CRL U.S. ALUMINUM HEADER EXTRUSION
C3	RT66311	CRL U.S. ALUMINUM GLASS STOP
C4	RT66511	CRL U.S. ALUMINUM HORIZONTAL MULLION
C5	RT66611	CRL U.S. ALUMINUM VERTICAL JAMB MULLION
C6	RT76911	CRL U.S. ALUMINUM FEMALE VERTICAL EXTRUSION
C7	RT76111	CRL U.S. ALUMINUM MALE VERTICAL EXTRUSION
C8	RT60011	CRL U.S. ALUMINUM HEAD COMPENSATION CHANNEL
C9	RT60011	CRL U.S. ALUMINUM STIFFENER PLATES
C10	RT60011	CRL U.S. ALUMINUM END DAMS
C11	RT60011	CRL U.S. ALUMINUM VERTICAL MULLION CAPS
C12	FR60011	CRL U.S. ALUMINUM FLUSH FILLER
C13	FR70111	CRL U.S. ALUMINUM SUB SILL EXTRUSION
C14	FR60211	CRL U.S. ALUMINUM GLAZING BEAD
W1	NR426	CRL 1/2" EPDM SPONGE CURTAINWALL EXTERIOR GASKET
W2	NR406	CRL CURTAINWALL GASKET
W3	NR606	CRL EXC. GLAZING GASKET DURO 70 EPDM
W4	VS200	CRL VINYL EQUALIZER
G1		.025 X .007 X .025 INSULATED GLASS (TEMPERED) ALUMINUM SPACER DUAL GLAZING
G2	SR663	NEOPRENE SETTING BLOCK
G3	SR634	CRL SETTING BLOCK - 1" GLAZING
G4	RN667	SETTING BLOCK CHAIR
H2	EF12	CRL CLOSED CELL 1/2" DIA. BACKER ROD
H3	BC	SILICONE BUILDING SEALANT
H4	RTY4060	CRL CLEAR RIVAR® NEUTRAL CURE SILICONE
H5		3/8" X 2" UG BOLT ASME B15.2.1 ZINC COATED ASTM 193
H6		
S1	ST261	1/16"x1" PHILLIPS WASHER HEAD SMS TYPE A6
S2	ST1811	#20x1/8" PHILLIPS CR. TEK. 2x.
W01	W0665	WATER DAM RT769
W02	W0667	WATER DAM RT761
W03	W0669	WATER DAM RT665 JAMB

TEST REQUIREMENTS	
AIR INFILTRATION:	< .06 CFM/SQ. FT. @ 6.24PSF
STATIC WATER:	12.0 PSF
DEFLECTION:	40 PSF
STRUCTURAL OVERLOAD:	60 PSF (0.2% permanent set)
TESTING SEQUENCE:	Air Water Dynamic Deflection Air Water Overload





2100 E. 38TH Street, Los Angeles, CA 90058
www.crlaurence.com


TT601 UNIT GLAZE
VERTICAL MULLION

Job Name:


Glazing Contractor:

DATE: 4-1-2015
DRAWN BY: GDO
CHECKED BY: XX
SCALE: AS SHOWN
JOB #: PTC467035


3 SIII



2 Horizontal



1 Head



RTV408 sealant applied at ext. full length of unit.
RTV408 sealant applied of interior full length of unit.

REVISIONS



CRL
ARCHITECTURAL PRODUCTS
C.R. LAURENCE CO.

2100 E. 38TH STREET, LOS ANGELES, CA 90058
www.crlaurence.com


TT601 UNIT GLAZE
VERTICAL MULLION

Job Name:


Glazing Contractor:

DATE: 4-1-2015
DRAWN BY: GDO
CHECKED BY: XX
SCALE: AS SHOWN
JOB #: PTC467035

SHT 3 OF 4



5 Unit Glazing
FWD-SKIP DEBRIDGE



4 Jamb
FWD-SKIP DEBRIDGE

(C1)
END DAM
AT
SUB SILL